



BILANS ROBÓT ZIEMNYCH - 1							
Pikieta	Pow.wyk	Pow.nas	Obj.wyk	Obj.nas	Całk.obj.wyk	Całk.obj.nas	Obj.netto
0+000.00	2.16	0.00	0.00	0.00	0.00	0.00	0.00
0+020.00	2.10	0.00	42.64	0.00	42.64	0.00	42.64
0+040.00	2.09	0.00	41.91	0.00	84.55	0.00	84.54
0+060.00	2.13	0.00	42.22	0.00	126.77	0.01	126.76
0+080.00	2.32	0.00	44.54	0.00	171.30	0.01	171.29
0+100.00	2.46	0.00	47.87	0.00	219.18	0.01	219.17
0+120.00	2.22	0.00	46.82	0.00	266.00	0.01	265.98
0+140.00	2.13	0.00	43.49	0.00	309.49	0.02	309.47
0+160.00	2.22	0.00	43.55	0.00	353.03	0.02	353.01
0+180.00	1.99	0.00	42.08	0.00	395.11	0.02	395.09
0+200.00	1.76	0.00	37.41	0.01	432.53	0.03	432.49
0+216.27	1.82	0.34	29.11	2.78	461.64	2.81	458.83
0+220.00	1.79	0.51	6.75	1.58	468.38	4.40	463.99
0+240.00	2.22	0.00	40.16	5.07	508.54	9.47	499.07
0+260.00	1.98	0.00	41.97	0.00	550.51	9.47	541.04
0+280.00	2.00	0.00	39.74	0.00	590.25	9.47	580.77
0+300.00	2.41	0.00	44.04	0.00	634.29	9.47	624.82
0+320.00	1.99	0.00	43.92	0.00	678.21	9.47	668.74
0+340.00	1.96	0.00	39.50	0.00	717.70	9.47	708.23
0+360.00	2.24	0.00	42.07	0.00	759.78	9.47	750.30
0+380.00	2.09	0.00	43.34	0.00	803.11	9.47	793.64
0+394.55	1.91	0.00	29.10	0.04	832.21	9.51	822.70

PRACOWNIA PROJEKTOWA P.W. "DAKAR" 26-600 RADOM  
Ul. Graniczna 17 kom. 693 058 040

PRZEBUDOWA DRUGI GMINNEJ NR 350309W  
W M. BARTODZIEJE GMINA JASTRZĘBIA  
NA ODCINKU 400M (OD DZIAŁKI NR 710/6 DO DZIAŁKI NR 696)

Przekroje do oszacowania ilości robót ziemnych

branża drogowąmgr inż. Janusz Karpeta  
mgr inż. Michał Rzymczyk

Str.:  
RADOM, 2024

Skala:  
1:100

Nr rys.:  
4