

WYKAZ STALI ZBROJENIOWEJ NR 1

Obiekt: BUDYNEK OSP										NR RYS.: 2,3,4,5		
Element: ŁAWY FUNDAMENTOWE, STROPY, WIENIEC ŻELB. - DACH GŁÓWNY												
Element	Poz.	Średnica		Długość	Liczba			Długość ogólna				
		St0S-b	RB500W		wkładek w 1 elem.	elem.	wkładek razem	St0S-b	RB500W			
		/mm/		/mm/	/sztuk/			ø 6	ø 8	ø 12	ø 16	ø 20
ławy fundamentowe	1		12	4250	12	1	12			51		
	2		12	11100	8		8			89		
	3		12	1800	5		5			9		
	4		12	750	12		12			9		
	5		12	5780	8		8			46		
	6		12	4750	4		4			19		
	7		12	7990	4		4			32		
	8		12	9130	4		4			37		
	9		12	11690	8		8			94		
	10	6		1360	32		32	44				
	11	6		1060	270		270	286				
	12		8	450	205		205		92			
	13		12	2260	8		8			18		
strop nad kotłownią	1		8	3100	47	1	47		146			
	2		8	7900	8		8		63			
	3		8	2200	17		17		37			
	4		8	1060	30		30		32			
	5		8	900	44		44		40			
	6		12	7300	1		1			7		
	7	6		37000	1		1	37				
	8		12	127000	1		1			127		
	9	6		1020	33		33	34				
	10	6		760	53		53	40				
strop nad parterem	1		8	8050	17	1	17		137			
	2		8	4650	59		59		274			
	3		8	2500	17		17		43			
	4		8	6850	10		10		69			
	5		8	3500	35		35		123			
	6		8	26500	1		1		27			
	7		8	1800	17		17		31			
	8		8	2000	44		44		88			
	9		12	2490	17		17			42		
	10		8	1200	25		25		30			
	11		8	2850	26		26		74			
	12		8	1000	25		25		25			
	13	6		221000	1		1	221				
	14		12	223000	1		1			223		
	15	6		760	160		160	122				
wieniec dach gł.	1		12	287000	1	1	1			287		
	2	6		940	250		250	235				
RAZEM							/m/	1018	1329	1090	0	0
CIĘŻAR 1mb PRĘTA							/kg/	0,222	0,395	0,888	1,580	2,470
CIĘŻAR OGÓLNY							/kg/	237	551	1016	0	0
RAZEM							/kg/	1805				